

Delta Pack

Ready to install

The performance of our Si-10 with ducting for install next-to the air conditioning unit.

Suitable for

- Up to 5.5 tons
- Wall mounted units

Performance

- 5 gph max. flow
- 33' max. discharge



Drain safe device



Easy installation







Delta Pack tech specs

	Max. Flow rate	5.0 gph	Safety switch
	Max. Discharge head	33ft; flow rate = 1 gph	Thermal protect
	Max. Pressure	46ft; flow rate = 0 gph	Operating condi
	Sound level at 3.3ft	22 dBA according to EN ISO 3744 (measured at LNE lab, pump operating with water, out of application)	Cover dimension
	Power supply	208-230 V ~ 50/60 Hz - 14 W (DP10UL02UN23)	Safety standards
	Insulation class	Double insulation	RoHS & WEEE di
	Detection levels	On: ${}^{23}\!/_{32}$ " / Off: ${}^{1}\!/_{2}$ " / Safety: ${}^{13}\!/_{16}$ "	Packaging

Safety switch	NC 8A resistive - 250 V	
Thermal protection	239°F auto-reset	
Operating conditions	100%: Continuous duty	
Cover dimensions	$L 5^{1}/_{8}$ " x W $5^{1}/_{8}$ " x H $2^{3}/_{8}$ "	
Duct dimensions	L 30" x W 3" x H 2 ³ / ₈ "	
Safety standards	UL / CSA certified by Intertek	
RoHS & WEEE directives	Compliant	
Packaging	3.4 lbs - L 30" x W $8^7/_8$ " x H $2^3/_8$ "	
Masterpack	10 pieces	







What's in the box

- Si-10 piston pump with clear pvc tube fitted with a premounted drain safe device
- 5' power cable: 2 power wires, 2 safety contact wires
- Vent tube
- 2-part elbow (base and cover)
- 30" of ductline
- Elbow / Fuct gasket
- Rubber elbow / split gasket •
- · Ceiling duct cover
- 20" flexible hose (for connection to the split)
- 6 screws and plugs, & 2 pipe clamps